ESTIMATE

[Your Business Name]
[Street address]
[City, State ZIP]
[email@yourbusiness.com]
[(555) 555-0123]

PREPARED FOR

[Client Name]
[Street address]
[City, State ZIP]
[client@email.com]
Job site: [Job address]

Estimate number:	EST-R-0001
Date:	10/27/2026
Valid until:	11/26/2026
Roof area:	[28 squares]
Pitch:	[6/12]

ITEM	UNIT PRICE	QUANTITY	AMOUNT
Tear-off, 1 layer asphalt shingles Per square	$85.00	28	**$2,380.00**
Synthetic underlayment, ice and water shield Per square	$48.00	28	**$1,344.00**
Architectural shingles, installed 28 squares + 10% waste	$165.00	31	**$5,115.00**
Drip edge, flashing and ridge vent	$1,150.00	1	**$1,150.00**
Dumpster, disposal and permit	$725.00	1	**$725.00**
Decking replacement allowance Up to 4 sheets; billed as used	$95.00	4	**$380.00**

NOTES/MEMO

Assumes one layer of shingles. Rotten decking replaced at $95 per sheet, billed as found. 10-year workmanship warranty. License no. [License number].

Subtotal:	$11,094.00
Estimated total:	**$11,094.00**

This is an estimate. The final amount may differ.